



Bill of Quantities

General Bid Info

Bidder Name	Bidder Email	IFB NO.	Submitted on	Submitted on

1. Provisional Sum


Procurement Item Details

SI.No.	Item Description	Unit	Quantity	Rate(NRs)	Rate in Words	Amount (NRs)
1	Insurance of works, plants, materials, loss and damage to equipments, Contractor's workmen and employees and third party insurance against damage to other persons and property(GCC 13)	Ls	1.00	100000.00		100000.00
2	Carry out additional tests for material and works as required and instructed by the Project Manager.(GCC 33.1)	Ps	1.00	100000.00		100000.00
3	Providing and installation of project signboards with size of 1.8 x 1.2 m as per specification and instruction of engineer.	Ls	1.00	5000.00		5000.00
			Total			205000.00

2 Construction work


2.1 Road Construction Work

SI.No.	Item Description	Unit	Quantity	Rate(NRs)	Rate in Words	Amount (NRs)
1	Compacting original ground supporting sub-grade Loosening of the ground upto a level of 500 mm below the sub-grade level, watered, graded and compacted in layers as per Drawing and Technical Specifications. (SS 1003 & 1005)	Cum	547.50			
2	Roadway excavation in all type of soil including disposal of excavated material at approved environmentally safe tipping sites, etc. all complete as per specification[SS 905]* By Mechanical Means	Cum	1568.59			
3	Roadway Excavation in ordinary rock as per Drawing and Technical specification, including all lift and	Cum	228.64			


 लोकहरी थापा
 प्रमुख प्रशासकीय अधिकृत




	lead as per Drawing and instruction of the engineer Mechanical Means					
4	Roadway Excavation in hard rock with rock breakers, including breaking rock, lifts and lead for disposal as per Drawing and Technical Specifications by Mechanical Means	Cum	152.06			
5	Earth work in excavation of foundation of structures in ordinary Soil, including construction of shoring and bracing, removal of stumps and other deleterious matter as per Drawing and Technical Specifications, etc. all complete as per specification[SS 907]*By Mechanical Means	Cum	414.77			
6	Providing, laying and levelling of dry stone soling works in the foundation/floor etc. all complete as per specification.	Cum	6.00			
	Providing and laying of Plain Cement Concrete (PCC) grade M20 in Foundation/sub-structure including formwork etc. all complete as per Drawing and Technical Specifications.	Cum	409.94			
7	Providing and laying of Reinforced Cement Concrete (RCC) grade M20 in Foundation/sub-structure including formwork etc. all complete as per Drawing and Technical Specifications.	Cum	10.00			
8	Providing and laying Reinforcement Fe 500 including cutting, bending, binding, fixing in position etc. all complete in foundation/sub-structure as per drawing and technical specification	Mt.	8.79			
9	Providing and placing plum concrete (Boulder mixed Concrete) with 60% M15/40 concrete and 40% boulders/stones as per specification, using concrete mixer and vibrator including formwork, curing, testing etc. all complete as per specification and drawing	Cum	429.39			


 लोकहरी थापा
 प्रमुख प्रशासकीय अधिकृत




10	Providing mechanically woven double twisted gabion boxes/crates /mattress with diaphragm including rolling, cutting and with lacing wire of Heavy zinc coated Hexagonal mesh type 100 mm x 120 mm, mesh wire 3 mm, selvaige wire 3.9 mm, lacing wire 2.4 mm ; assembling Gabion boxes mattresses, palcing in position including stretching, forming compartments; tying with bracing wires and tie wires; tying down the lid complete; and providing and filling stone / boulder in gabion boxes / mattresses etc. including dressing, beding, bonding and all transporation as per specification. [SS 2402]*(Box size: 1.5mx1mx1m)	Cum	9.00			
11	Providing mechanically woven double twisted gabion boxes/crates /mattress with diaphragm including rolling, cutting and with lacing wire of Heavy zinc coated Hexagonal mesh type 100 mm x 120 mm, mesh wire 3 mm, selvaige wire 3.9 mm, lacing wire 2.4 mm ; assembling Gabion boxes mattresses, palcing in position including stretching, forming compartments; tying with bracing wires and tie wires; tying down the lid complete; and providing and filling stone / boulder in gabion boxes / mattresses etc. including dressing, beding, bonding and all transporation as per specification. [SS 2402]*(Box size: 2mx1mx1m)	Cum	122.00			


 लोकहरी थापा
 प्रमुख प्रशासकीय अधिकृत



12	Providing mechanically woven double twisted gabion boxes/crates /mattress with diaphragm including rolling, cutting and with lacing wire of Heavy zinc coated Hexagonal mesh type 100 mm x 120 mm, mesh wire 3 mm, selvage wire 3.9 mm, lacing wire 2.4 mm ; assembling Gabion boxes mattresses, placing in position including stretching, forming compartments; tying with bracing wires and tie wires; tying down the lid complete; and providing and filling stone / boulder in gabion boxes / mattresses etc. including dressing, bedding, bonding and all transportation as per specification. [SS 2402]*(Box size: 3mx1mx1m)	Cum	312.00			
13	Geotextile work	Sq.m	219.00			
14	75mm HDPE(PN6) pipe for weep hole	Mtr.	100.00			
					Total Amount	
Total of Procurement items						
Total item price						
13% VAT						
Total Ps Amount						
Grand Total						
Grand Total Amount (In Words):						


 लोकहरी थापा
 प्रमुख प्रशासकीय अधिकृत