

Bid Addendum Report

Bagmati Rural Municipality

Bagmati Rural Municipality
Bhattedada
Lalitpur
Bagmati Province
Bagmati Gaupalika
Nepal

Addendum No: 1

Published On: 03-11-2025 10:00

Invitation No: BAGL/NCB/WORKS/082/083-03

Dated On: 16-10-2025 10:00

Following changes are made in the bid document

Chapter: General Information

Sl. No.	Relavant Clause No / Name	Existing Clause	Modified Clause
1	Clarification Submission Date	Not Provided in Bid Document	2025-11-03 10:00:00
2	Bid Submission DeadLine	2025-11-16 11:00:00	2025-11-17 16:00:00
3	Bid Opening Date	2025-11-16 14:00:00	2025-11-18 12:00:00
4	Bid Opening Address	agmati Rural Municipality Bhattedanda, Lalitpur	Bagmati Rural Municipality Bhattedanda, Lalitpur
5	Bid Security Fee	500000.00	325000.00

Chapter: Bill of Quantities

1 Provisional Sum						
Procument Item Details						
SL. No	Item Description	Unit	Quantity	Unit Rate(in NPR)	Amount(in NPR)	
1	Providing and installation of project signboards with size of 1.8 x 1.2 m as per specification and instruction of engineer.	PS	1	5000	5000	
2	Reconstruction and Relocation of damaged public utility services(Electricity,watersupply,telecom,etc) , supply of miscellaneous items(Survey and lab equipments etc.) required, engineers facilities, traffic management and traffic safety etc. during construction all complete as directed by Engineer .	PS	1	30000	30000	
3	Carry out additional tests for material and works as required and instructed by the Project Manager.(GCC 33.1)	PS	1	50000	50000	
4	Insurance of works, plants, materials, loss and damage to equipments, Contractor's workmen and employees and third party insurance against damage to other persons and property(GCC 13)	PS	1	65000	65000	
2 Construction work						
2.1 Road Construction Work						
Procument Item Details						
SL. No	Item Description	Unit	Quantity	Bidder's Rate(NPR)	Bidder's Rate (in words)	Total Amount(NPR)
1	Providing and installation of 150 mm * 150 mm 1. 5 m long delineators (road way indicators, hazard markers, object markers), 80-100 cm high above ground level, painted black and white in 20 cm wide strips, buried or pressed into the ground and conforming to the drawings and Technical Specifications.	Nos	100.0			
2	Roadway excavation in all type of soil including disposal of excavated material at approved environmentally safe tipping sites, etc. all complete as per specification[SS 905]* By Mechanical Means	Cum	30685.49			
3	Roadway Excavation in ordinary rock as per Drawing and Technical specification, including all lift and lead as per Drawing and instruction of the engineer Mechanical Means	Cum	954.45			
4	Roadway Excavation in hard rock with rock breakers, including breaking rock, lifts and lead for disposal as per Drawing and Technical Specifications by Mechanical Means	Cum	174.98			

Procurement Item Details						
SL. No	Item Description	Unit	Quantity	Bidder's Rate(NPR)	Bidder's Rate (in words)	Total Amount(NPR)
5	Removal of unserviceable soil including excavation,loading and disposal up to a lead/tranportation at safe tipping site etc. all complete (905)	Cum	306.85			
6	Earth work in excavation of foundation of structures & Drain in Ordinary Soil, including construction of shoring and bracing, removal of stumps and other deleterious matter and backfilling with approved Material as per Drawing and Technical Specifications, etc. all complete as per specification[SS 907]* By 80% Mechancical Means and 20% Manual Means	Cum	194.76			
7	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications.	Cum	132.69			
8	Providing and laying of plain cement concrete machine mixed M15/40 for the Structure/Drain etc. including F2 Finishing form work, compaction, curing, testing and relevant lead . etc. all complete as per Drawing and Technical specification.	Cum	150.84			
9	Providing and laying of Plain Cement Concrete M 10 (or1:3:6 for nominal mix) in Foundation complete as per Drawing and Technical Specifications.	Cum	16.23			
10	Providing and laying of Plain Cement Concrete (PCC) grade M20 in Foundation/sub-structure including formwork etc. all complete as per Drawing and Technical Specifications.	Cum	112.0			
11	Providing and laying of Random Rubble Stone Masonry Work in Cement Mortar 1:4 in structure complete as per Drawing and Technical Specifications.	Cum	85.2			
12	Providing and laying Reinforcement Fe 500 including cutting, bending, binding, fixing in position etc. all complete in super-structure complete as per drawing and technical specifications.	Mt	0.63			

Procurement Item Details						
SL. No	Item Description	Unit	Quantity	Bidder's Rate(NPR)	Bidder's Rate (in words)	Total Amount(NPR)
13	Providing mechanically woven double twisted gabion boxes/crates /mattress with diaphragm including rolling, cutting and with lacing wire of Heavy zinc coated Hexagonal mesh type 100 mm x 120 mm, mesh wire 3 mm, selvage wire 3.9 mm, lacing wire 2.4 mm ; assembling Gabion boxes mattresses, palcing in position including stretching, forming compartments; tying with bracing wires and tie wires; tying down the lid complete; and providing and filling stone / boulder in gabion boxes / mattresses etc. including dressing, beding, bonding and all transporation as per specification. (2x1x1 m) [SS 2402]*	Cum	224.0			
14	Providing mechanically woven double twisted gabion boxes/crates /mattress with diaphragm including rolling, cutting and with lacing wire of Heavy zinc coated Hexagonal mesh type 100 mm x 120 mm, mesh wire 3 mm, selvage wire 3.9 mm, lacing wire 2.4 mm ; assembling Gabion boxes mattresses, palcing in position including stretching, forming compartments; tying with bracing wires and tie wires; tying down the lid complete; and providing and filling stone / boulder in gabion boxes / mattresses etc. including dressing, beding, bonding and all transporation as per specification. (1.5x1x1 m) [SS 2402]*	Cum	36.0			
15	Providing, laying, fixing in positions of Geo-textile (filter fabrics). [SS 2404]*	Sqm	142.0			
16	Providing and Laying Reinforced cement concrete 900 mm internal dia. NP3 Flush jointed pipe for culverts including fixing with cement mortar 1:2 as per Drawing and Technical Specifications.	Rm	10.0			
17	Providing and Laying Reinforced cement concrete 600 mm internal dia. NP3 Flush jointed pipe for culverts including fixing with cement mortar 1:2 as per Drawing and Technical Specifications.	Rm	10.0			
18	UPVC pipe 110 mm 2.5 kg/cm2 (Weep Hole)	Rm	125.0			